#### **Deutsches Institut für Bautechnik**

#### Zulassungsstelle für Bauprodukte und Bauarten

#### **Bautechnisches Prüfamt**

Eine vom Bund und den Ländern gemeinsam getragene Anstalt des öffentlichen Rechts

Kolonnenstraße 30 B D-10829 Berlin Tel.: +493078730-0 Fax: +493078730-320 E-Mail: dibt@dibt.de www.dibt.de





Mitglied der EOTA Member of EOTA

# **European Technical Approval ETA-02/0024**

English translation prepared by DIBt - Original version in German language

Handelsbezeichnung

Trade name

Injektionssystem fischer FIS V Injection System fischer FIS V

Zulassungsinhaber Holder of approval

fischerwerke GmbH & Co. KG Otto-Hahn-Straße 15

79211 Denzlingen DEUTSCHLAND

Zulassungsgegenstand und Verwendungszweck

Generic type and use of construction product

Geltungsdauer: vom Validity:

from bis

to verlängert extended

vom from bis

to

Herstellwerk Manufacturing plant ungerissenen Beton

Bonded anchor in the size of M6 to M30 for use in non-cracked concrete

Verbunddübel in den Größen M6 bis M30 zur Verankerung im

12 March 2012

29 October 2012

30 October 2012

30 October 2017

fischerwerke

Diese Zulassung umfasst This Approval contains

38 Seiten einschließlich 29 Anhänge 38 pages including 29 annexes





Page 2 of 38 | 30 October 2012

#### I LEGAL BASES AND GENERAL CONDITIONS

- This European technical approval is issued by Deutsches Institut für Bautechnik in accordance with:
  - Council Directive 89/106/EEC of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products<sup>1</sup>, modified by Council Directive 93/68/EEC<sup>2</sup> and Regulation (EC) N° 1882/2003 of the European Parliament and of the Council<sup>3</sup>;
  - Gesetz über das In-Verkehr-Bringen von und den freien Warenverkehr mit Bauprodukten zur Umsetzung der Richtlinie 89/106/EWG des Rates vom 21. Dezember 1988 zur Angleichung der Rechts- und Verwaltungsvorschriften der Mitgliedstaaten über Bauprodukte und anderer Rechtsakte der Europäischen Gemeinschaften (Bauproduktengesetz - BauPG) vom 28. April 1998<sup>4</sup>, as amended by Article 2 of the law of 8 November 2011<sup>5</sup>;
  - Common Procedural Rules for Requesting, Preparing and the Granting of European technical approvals set out in the Annex to Commission Decision 94/23/EC<sup>6</sup>;
  - Guideline for European technical approval of "Metal anchors for use in concrete Part 5: Bonded anchors", ETAG 001-05.
- Deutsches Institut für Bautechnik is authorized to check whether the provisions of this European technical approval are met. Checking may take place in the manufacturing plant. Nevertheless, the responsibility for the conformity of the products to the European technical approval and for their fitness for the intended use remains with the holder of the European technical approval.
- This European technical approval is not to be transferred to manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those indicated on page 1 of this European technical approval.
- This European technical approval may be withdrawn by Deutsches Institut für Bautechnik, in particular pursuant to information by the Commission according to Article 5(1) of Council Directive 89/106/EEC.
- Reproduction of this European technical approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of Deutsches Institut für Bautechnik. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European technical approval.
- The European technical approval is issued by the approval body in its official language. This version corresponds fully to the version circulated within EOTA. Translations into other languages have to be designated as such.
- Official Journal of the European Communities L 40, 11 February 1989, p. 12
- Official Journal of the European Communities L 220, 30 August 1993, p. 1
- Official Journal of the European Union L 284, 31 October 2003, p. 25
- Bundesgesetzblatt Teil I 1998, p. 812
- 5 Bundesgesetzblatt Teil I 2011, p. 2178
- Official Journal of the European Communities L 17, 20 January 1994, p. 34

Z72854.12 8.06.01-237/12



Page 3 of 38 | 30 October 2012

#### II SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

#### 1 Definition of product/ products and intended use

#### 1.1 Definition of the construction product

The Injection system fischer FIS V is a bonded anchor (injection type) consisting of a mortar cartridge with fischer injection mortar FIS V, FIS VW or FIS VS and a steel element. The steel elements are either

- fischer anchor rods in the range of M6 to M30 or
- fischer internal threaded anchor RG MI in the range of M8 to M20 or
- Reinforcing bar in the range of Ø 8 to Ø 28 or
- fischer rebar anchor FRA in the range of 12 to 24.

The steel element is placed into a drilled hole filled with injection mortar and is anchored via the bond between steel element, injection mortar and concrete.

An illustration of the product and intended use is given in Annexes 1 and 2.

#### 1.2 Intended use

The anchor is intended to be used for anchorages for which requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 of Council Directive 89/106 EEC shall be fulfilled and failure of anchorages made with these products would cause risk to human life and/or lead to considerable economic consequences. Safety in case of fire (Essential Requirement 2) is not covered in this European technical approval. The anchor is to be used only for anchorages subject to static or quasi-static loading in reinforced or unreinforced normal weight concrete of strength classes C20/25 at minimum and C50/60 at most according to EN 206:2000-12.

The anchor may be used in non-cracked concrete only.

The anchor may be installed in dry or wet concrete. The internal threaded anchor RG MI and the fischer-anchor rod in the range of M12 to M30 with coaxial cartridges of sizes 380 ml, 400 ml and 410 ml may be installed in flooded holes excepting sea water.

The drill hole shall be made by hammer drilling or compressed air drilling.

The anchor may be used in the following service temperature ranges:

Temperature range I: -40 °C to +80 °C (max long term temperature +50 °C and

max short term temperature +80 °C)

Temperature range II: -40 °C to +120 °C (max long term temperature +72 °C and

max short term temperature +120 °C)

#### Elements made of zinc coated steel:

The element made of electroplated or hot-dipped galvanised steel may only be used in structures subject to dry internal conditions.

Z72854.12 8.06.01-237/12



#### Page 4 of 38 | 30 October 2012

#### Elements made of stainless steel A4:

The element made of stainless steel may be used in structures subject to dry internal conditions and also in structures subject to external atmospheric exposure (including industrial and marine environment), or exposure in permanently damp internal conditions, if no particular aggressive conditions exist. Such particular aggressive conditions are e.g. permanent, alternating immersion in seawater or the splash zone of seawater, chloride atmosphere of indoor swimming pools or atmosphere with extreme chemical pollution (e.g. in desulphurization plants or road tunnels where de-icing materials are used).

#### Elements made of high corrosion resistant steel C:

The element made of high corrosion resistant steel may be used in structures subject to dry internal conditions and also in structures subject to external atmospheric exposure, in permanently damp internal conditions or in other particular aggressive conditions. Such particular aggressive conditions are e.g. permanent, alternating immersion in seawater or the splash zone of seawater, chloride atmosphere of indoor swimming pools or atmosphere with chemical pollution (e.g. in desulphurization plants or road tunnels where de-icing materials are used).

#### Elements made of reinforcing bars:

Post-installed reinforcing bars may only be used as anchors. Such applications are e.g. concrete overlay or shear dowel connections or the connections of a wall predominantly loaded by shear and compression forces with the foundation, where the reinforcing bars act as dowels to take up shear forces. Connections with post-installed reinforcing bars in concrete structures designed in accordance with EN1992-1-1: 2004 are not covered by this European technical approval.

The provisions made in this European technical approval are based on an assumed working life of the anchor of 50 years. The indications given on the working life cannot be interpreted as a guarantee given by the producer, but are to be regarded only as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

#### 2 Characteristics of the product and methods of verification

#### 2.1 Characteristics of product

The anchor corresponds to the drawings and provisions given in Annexes 1 to 7. The characteristic material values, dimensions and tolerances of the anchor not indicated in Annexes 1 to 7 shall correspond to the respective values laid down in the technical documentation of this European technical approval.

The characteristic anchor values for the design of anchorages are given in Annexes 10 to 29.

The two components of the fischer injection mortar FIS V, FIS VW or FIS VS are delivered in unmixed condition in shuttle cartridges or in coaxial cartridges according to Annex 1. Each cartridge is marked with the imprint "fischer FIS V", "fischer FIS VW" or "fischer FIS VS" with processing notes, shelf life, curing time, processing time (depending on temperature), hazard code.

Each fischer anchor rod is marked with the property class in accordance with Annex 3.

Z72854 12 8 06 01-237/12

The technical documentation of this European technical approval is deposited at the Deutsches Institut für Bautechnik and, as far as relevant for the tasks of the approved bodies involved in the attestation of conformity procedure, is handed over to the approved bodies.



# Extension of validity of the European technical approval ETA-02/0024

Page 5 of 38 | 30 October 2012

English translation prepared by DIBt

Each fischer internal threaded anchor RG MI is marked with the marking of steel grade and length in accordance with Annex 4. Each fischer internal threaded anchor RG MI made of stainless steel is marked with the additional letter "A4". Each fischer internal threaded anchor RG MI made of high corrosion resistant steel is marked with the additional letter "C".

Each fischer rebar anchor FRA is marked with the identifying mark of the producer and the trade name according to Annex 7.

Elements made of reinforcing bars shall comply with the specifications given in Annex 6.

The marking of embedment depth may be done on jobsite.

#### 2.2 Methods of verification

The assessment of fitness of the anchor for the intended use in relation to the requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 has been made in accordance with the "Guideline for European technical approval of Metal Anchors for use in concrete", Part 1 "Anchors in general" and Part 5 "Bonded anchors" on the basis of Option 7.

In addition to the specific clauses relating to dangerous substances contained in this European technical approval, there may be other requirements applicable to the products falling within its scope (e.g. transposed European legislation and national laws, regulations and administrative provisions). In order to meet the provisions of the Construction Products Directive, these requirements need also to be complied with, when and where they apply.

#### 3 Evaluation and attestation of conformity and CE marking

#### 3.1 System of attestation of conformity

According to the Decision 96/582/EG of the European Commission<sup>8</sup> system 2(i) (referred to as System 1) of the attestation of conformity applies.

This system of attestation of conformity is defined as follows:

System 1: Certification of the conformity of the product by an approved certification body on the basis of:

- (a) Tasks for the manufacturer:
  - (1) factory production control;
  - (2) further testing of samples taken at the factory by the manufacturer in accordance with a prescribed control plan;
- (b) Tasks for the approved body:
  - (3) initial type-testing of the product;
  - (4) initial inspection of factory and of factory production control;
  - (5) continuous surveillance, assessment and approval of factory production control.

Note: Approved bodies are also referred to as "notified bodies".

Z72854.12 8.06.01-237/12

Official Journal of the European Communities L 254 of 08.10.1996



Page 6 of 38 | 30 October 2012

#### 3.2 Responsibilities

#### 3.2.1 Tasks for the manufacturer

#### 3.2.1.1 Factory production control

The manufacturer shall exercise permanent internal control of production. All the elements, requirements and provisions adopted by the manufacturer shall be documented in a systematic manner in the form of written policies and procedures, including records of results performed. This production control system shall insure that the product is in conformity with this European technical approval.

The manufacturer may only use initial/raw/constituent materials stated in the technical documentation of this European technical approval.

The factory production control shall be in accordance with the control plan which is part of the technical documentation of this European technical approval. The control plan is laid down in the context of the factory production control system operated by the manufacturer and deposited with Deutsches Institut für Bautechnik.<sup>9</sup>

The results of factory production control shall be recorded and evaluated in accordance with the provisions of the control plan.

#### 3.2.1.2 Other tasks for the manufacturer

The manufacturer shall, on the basis of a contract, involve a body which is approved for the tasks referred to in section 3.1 in the field of anchors in order to undertake the actions laid down in section 3.2.2 For this purpose, the control plan referred to in sections 3.2.1.1 and 3.2.2 shall be handed over by the manufacturer to the approved body involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this European technical approval.

#### 3.2.2 Tasks for the approved bodies

The approved body shall perform the

- initial type-testing of the product,
- initial inspection of factory and of factory production control,
- continuous surveillance, assessment and approval of factory production control,

in accordance with the provisions laid down in the control plan.

The approved body shall retain the essential points of its actions referred to above and state the results obtained and conclusions drawn in a written report.

The approved certification body involved by the manufacturer shall issue an EC certificate of conformity of the product stating the conformity with the provisions of this European technical approval.

In cases where the provisions of the European technical approval and its control plan are no longer fulfilled the certification body shall withdraw the certificate of conformity and inform Deutsches Institut für Bautechnik without delay.

#### 3.3 CE marking

The CE marking shall be affixed on each packaging of the anchor. The letters "CE" shall be followed by the identification number of the approved certification body, where relevant, and be accompanied by the following additional information:

- the name and address of the producer (legal entity responsible for the manufacture),
- the last two digits of the year in which the CE marking was affixed,

Z72854.12 8.06.01-237/12

,

The control plan is a confidential part of the European technical approval and only handed over to the approved body involved in the procedure of attestation of conformity. See section 3.2.2.



# Extension of validity of the European technical approval ETA-02/0024

Page 7 of 38 | 30 October 2012

English translation prepared by DIBt

- the number of the EC certificate of conformity for the product,
- the number of the European technical approval,
- the number of the guideline for European technical approval,
- use category (ETAG 001-1, Option 7),
- size.

#### 4 Assumptions under which the fitness of the product for the intended use was favourably assessed

#### 4.1 Manufacturing

The European technical approval is issued for the product on the basis of agreed data/information, deposited with Deutsches Institut für Bautechnik, which identifies the product that has been assessed and judged. Changes to the product or production process, which could result in this deposited data/information being incorrect, should be notified to Deutsches Institut für Bautechnik before the changes are introduced. Deutsches Institut für Bautechnik will decide whether or not such changes affect the approval and consequently the validity of the CE marking on the basis of the approval and if so whether further assessment or alterations to the approval shall be necessary.

#### 4.2 Design of anchorages

The fitness of the anchor for the intended use is given under the following conditions:

The anchorages are designed in accordance with the

EOTA Technical Report TR 029 "Design of bonded anchors" 10

or in accordance with the

CEN/TS 1992-4-5 "Design of fastenings for use in concrete", Part 4-5: "Post-installed fasteners - Chemical systems",

under the responsibility of an engineer experienced in anchorages and concrete work.

Post-installed reinforcing bars may only be used as anchors. The basic assumptions for the design according to anchor theory shall be observed. This includes the consideration of tension and shear loads and the corresponding failure modes as well as the assumption that the base material (concrete structural element) remains essentially in the serviceability limit state (either non-cracked or cracked) when the connection is loaded to failure. Such applications are e.g. concrete overlay or shear dowel connections or the connections of a wall predominantly loaded by shear and compression forces with the foundation, where the reinforcing bars act as dowels to take up shear forces. Connections with reinforcing bars in concrete structures designed in accordance with EN 1992-1-1:2004 (e.g. connection of a wall loaded with tension forces in one layer of the reinforcement with the foundation) are not covered by this European technical approval.

For the fischer internal threaded anchor RG MI fastening screws or threaded rods made of appropriate steel and strength class acc. to Annex 5 shall be specified. The minimum and maximum thread engagement length I<sub>E</sub> of the fastening screw or the threaded rod for installation of the fixture shall be met the requirements according to Annex 4, Table 2. The length of the fastening screw or the threaded rod shall be determined depending on thickness of fixture, admissible tolerances, available thread length and minimum and maximum thread engagement length I<sub>E</sub>.

Z72854.12 8.06.01-237/12

10

The Technical Report TR 029 "Design of Bonded Anchors" is published in English on EOTA website www.eota.eu.



# Extension of validity of the European technical approval ETA-02/0024

Page 8 of 38 | 30 October 2012

English translation prepared by DIBt

Verifiable calculation notes and drawings are prepared taking account of the loads to be anchored.

The position of the anchor is indicated on the design drawings (e.g. position of the anchor relative to reinforcement or to supports, etc.).

#### 4.3 Installation of anchors

The fitness for use of the anchor can only be assumed if the anchor is installed as follows:

- anchor installation carried out by appropriately qualified personnel and under the supervision of the person responsible for technical matters of the site,
- use of the anchor only as supplied by the manufacturer without exchanging the components of an anchor,
- anchor installation in accordance with the manufacturer's specifications and drawings using the tools indicated in the technical documentation of this European technical approval.
- commercial standard threaded rods, washers and hexagon nuts may also be used if the following requirements are fulfilled:
  - material, dimensions and mechanical properties of the metal parts according to the specifications given in Annex 5, Table 3,
  - confirmation of material and mechanical properties of the metal parts by inspection certificate 3.1 according to EN 10204:2004, the documents should be stored,
  - marking of the threaded rod with the envisage embedment depth. This may be done by the manufacturer of the rod or the person on jobsite.
- reinforcing bars shall comply with specifications given in Annex 6.
- checks before placing the anchor to ensure that the strength class of the concrete in which the anchor is to be placed is in the range given and is not lower than that of the concrete to which the characteristic loads apply.
- check of concrete being well compacted, e.g. without significant voids,
- marking and keeping the effective anchorage depth,
- edge distance and spacing not less than the specified values without minus tolerances,
- positioning of the drill holes without damaging the reinforcement,
- drilling by hammer drilling or compressed air drilling,
- in case of aborted drill hole: the drill hole shall be filled with mortar.
- The anchor may be installed in dry or wet concrete. The internal threaded anchor RG MI and the fischer-anchor rod in the range of M12 to M30 with coaxial cartridges of sizes 380 ml, 400 ml and 410 ml may be installed in flooded holes excepting sea water,
- cleaning the drill hole and installation in accordance with Annexes 8 and 9,
- the anchor component installation temperature shall be at least 0 °C (fischer FIS VW) and +5 °C (FIS V and FIS VS); during curing of the chemical mortar the temperature of the concrete must not fall below -5 °C (fischer FIS V, FIS VW) and 0 °C (FIS VS); observing the curing time according to Annex 5, Table 4 until the anchor may be loaded,
- for installation in bore holes  $h_0 > 150$  mm extension hoses acc. Annex 1 shall be used,
- Fastening screw or threaded rods (including nut and washer) must comply with the appropriate material and strength class of the fischer internal threaded anchor RG MI.
- installation torque moments are not required for functioning of the anchor. However, the torque moments given in Annexes 3 to 7 must not be exceeded.

Z72854.12 8.06.01-237/12



Page 9 of 38 | 30 October 2012

#### 5 Indications to the manufacture

#### 5.1 Responsibility of the manufacturer

It is in the responsibility of the manufacturer to ensure that the information on the specific conditions according to 1 and 2 including Annexes referred to as well as sections 4.2, 4.3 and 5.2 is given to those who are concerned. This information may be made by reproduction of the respective parts of the European technical approval. In addition all installation data shall be shown clearly on the package and/or on an enclosed instruction sheet, preferably using illustration(s).

The minimum data required are:

- drill bit,
- hole depth,
- diameter of anchor rod,
- minimum effective anchorage depth,
- information on the installation procedure, including cleaning of the hole with the cleaning equipments, preferably by means of an illustration,
- anchor component installation temperature.
- material and property class of metal parts acc. to Annex 5, Table 3,
- ambient temperature of the concrete during installation of the anchor,
- admissible processing time (open time) of a cartridge,
- curing time until the anchor may be loaded as a function of the ambient temperature in the concrete during installation,
- maximum torque moment,
- identification of the manufacturing batch.

All data shall be presented in a clear and explicit form.

#### 5.2 Recommendations concerning packaging, transport and storage

The injection cartridges shall be protected against sun radiation and shall be stored according to the manufacture's installation instructions in dry condition at temperatures of at least +5 °C to not more than +25 °C.


Mortar cartridges with expired shelf life must no longer be used.

The anchor shall only be packaged and supplied as a complete unit. Mortar cartridges may be packed separately from metal parts.

Georg Feistel beglaubigt:
Head of Department Aksünger

Z72854.12 8.06.01-237/12













Table 1: Installation parameters fischer anchor rods

Size of anchor			[-]	M6	M8	M10	M12	M16	M20	M24	M30
Nominal drill bi	t diameter	$d_{\scriptscriptstyle{\mathrm{O}}}$	[mm]	8	10	12	14	18	24	28	35
Drill hole depth	1	h <sub>o</sub>	[mm]				h <sub>o</sub> =	h <sub>ef</sub>			
Effective ancho	rage	h <sub>ef,min</sub>	[mm]	50	60	60	70	80	90	96	120
depth		h <sub>ef,max</sub>	[mm]	72	160	200	240	320	400	480	600
Minimum spac and minimum edge distance	ing s <sub>m</sub>	nin= c <sub>min</sub>	[mm]	40	40	45	55	65	85	105	140
Diameter of clearance	pre-position anchorage	ned <sub>d,</sub>	[mm]	7	9	12	14	18	22	26	33
hole in the fixture 1)	push-throu anchorage		[mm]	9	11	14	16	20	26	30	40
Minimum thick of concrete me		h <sub>min</sub>	[mm]		h <sub>ef</sub> + 30	(≥100)			h <sub>ef</sub> +	- 2d <sub>o</sub>	
Maximum torq	ue	T <sub>inst,max</sub>	[Nm]	5	10	20	40	60	120	150	300
Thickness of fixture		t <sub>fix,min</sub>	[mm]				(	)			
		t <sub>fix,max</sub>	[mm]				30	00			

<sup>&</sup>lt;sup>1)</sup>For bigger clearance holes in fixture see chapter 1.1 of the TR 029.

#### fischer anchor rod



## Marking:

Property class 8.8 or high corrosion-resistant steel C, property class 80: • Stainless steel A4, property class 50 and high corrosion-resistant steel C, property class 50: • •

# Application range and intended use

		max. long term temperature	max. short term temperature
Temperature range I:	-40°C to +80°C	+50°C	+80°C
Temperature range II:	-40°C to +120°C	+72°C	+120°C

Intended use	dry concrete wet concrete		flooded hole <sup>1)</sup>		
Anchor rods	M8 – M30		M12 – M30		
Internal threaded anchors RG MI	M8 – M20				

<sup>1)</sup> Only coaxial cartridge 380 ml, 400 ml and 410 ml.


fischer injection system FIS V	
fischer anchor rods Installation parameters and dimensions Application range and intended use	Annex 3




Table 2: Installation parameters for fischer internal threaded anchors RG MI

Size of anchor		M8	M10	M12	M16	M20
Diameter of anchor	d <sub>H</sub> [mm]	12	16	18	22	28
Nominal drill bit diameter	d <sub>o</sub> [mm]	14	18	20	24	32
Length of anchor	L <sub>H</sub> [mm]	90	90	125	160	200
Effective anchorage depth $h_{\rm ef}$ and drill hole depth $h_{\rm o}$	$h_{ef} = h_{O} [mm]$	90	90	125	160	200
Minimum spacing and edge distance	$s_{min} = c_{min}$ [mm]	55	65	75	95	125
Diameter of clearence hole in the fixture	d <sub>f</sub> [mm]	9	12	14	18	22
Minimum thickness of concrete member	h <sub>min</sub> [mm]	120	125	165	205	260
Communications	I <sub>E,min</sub> [mm]	8	10	12	16	20
Screw-in depth	I <sub>E,max</sub> [mm]	18	23	26	35	45
Maximum troque moment	T <sub>inst,max</sub> [Nm]	10	20	40	80	120

## fischer internal threaded anchor RG MI





Marking: anchor size

e.g.: M10

Stainless steel additional A4

e.g.: M10 A4

High corrosion-resistant steel additional C

e.g.: M10 C

fischer injection system FIS V	
fischer internal threaded anchors RG MI Installation parameters and dimensions	Annex 4



Table 3: Materials: anchor rods, washers, hexagon nuts and screws

Designation		Materials	
	Steel, zinc plated	Stainless steel A4	high corrosion-resistant steel C
anchor rod	Property class 5.8 or 8.8; EN ISO 898-1 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised EN ISO 10684 f <sub>uk</sub> ≤ 1000 N/mm <sup>2</sup> A <sub>5</sub> > 8%	Property class 50, 70 or 80 EN ISO 3506 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362 EN 10088 or 1.4062 pr EN 10088:2011 $f_{uk} \le 1000 \text{ N/mm}^2$ $A_5 > 8\%$	Property class 50 or 80 EN ISO 3506 or property class 70 with $f_{yk} = 560 \text{ N/mm}^2$ 1.4565; 1.4529 EN 10088 $f_{uk} \le 1000 \text{ N/mm}^2$ $A_5 > 8\%$
Washer EN ISO 7089	zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised EN ISO 10684	1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362 EN 10088	1.4565;1.4529 EN 10088
Hexagon nut according to EN ISO 4032	Property class 5 or 8; EN ISO 898-2 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised EN ISO 10684	Property class 50, 70 or 80 EN ISO 3506 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362 EN 10088	Property class 50, 70 or 80 EN ISO 3506 1.4565; 1.4529 EN 10088
Screw or anchor rods for internal- threaded anchors RG MI	Property class 5.8 or 8.8; EN ISO 898-1 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised EN ISO 10684	Property class 70 EN ISO 3506 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362 EN 10088	Property class 70 EN ISO 3506-1 1.4565; 1.4529 EN 10088

Table 4: Maximum processing time of the mortar and minimum curing time (During the curing time of the mortar the concrete temperature may not fall below the listed minimum temperature).

Temperature at anchoring base				System- temperature (mortar)	Maximum processing time twork [minutes]		
[ °C ]	FIS VW	FIS V	FIS VS	[°C]	FIS VW	FIS V	FIS VS
-5 to ±0	3 hours	24 hours		0	5		
>±0 to +5	3 hours	3 hours	6 hours	+ 5	5	13	
>+5 to +10	50	90	3 hours	+ 10	3	9	20
>+10 to +20	30	60	2 hours	+ 20	1	5	10
>+20 to +30		45	60	+ 30		4	6
>+30 to +40		35	30	+ 40		2	4

<sup>&</sup>lt;sup>1)</sup> For wet concrete the curing time must be doubled.

fischer injection system FIS V	
Materials Processing time and curing time	Annex 5




d = nominal bar size

Table 5:	Installation	parameters	reinforcing	bars

Rebar diameter	d [mm]	81)	10¹)	121)		14	16	20	25	28
Nominal drill bit diameter	d <sub>o</sub> [mm]	(10)12	(12)14	(14)	16	18	20	25	30	35
Drill hole depth	h <sub>o</sub> [mm]		h <sub>o</sub> = h <sub>ef</sub>							
Effective	h <sub>ef,min</sub> [mm]	60	60	7	0	75	80	90	100	112
anchorage depth	h <sub>ef,max</sub> [mm]	160	200	24	10	280	320	400	500	560
Minimum spacing and minimum edge distance	s <sub>min</sub> = c <sub>min</sub> [mm]	40	45	5	5	60	65	85	110	130
Minimum thickness of concrete mer	h <sub>min</sub> [mm] mber	h <sub>ef</sub> +	30 ≥ 100		$h_{ef} + 2d_{o}$					

<sup>1)</sup> Both drill bit diameters can be used

## Reinforcing bar



# Properties of reinforcement: refer to EN 1992-1-1 Annex C, Table C.1 and C.2N

Produkt form	Non-zinc-plated bars and de-coiled rod			
Class		В	С	
Characteristic yield strength fyk	400 to	600		
Minimum value of $k = (f_t / f_{yk})$	≥ 1,08	≥ 1,15 < 1,35		
Characteristic strain at maximum	≥ 5,0	≥ 7,5		
Bendability property		Bend / Rebendtest		
Maximum deviation from nominal mass (individual bar) [%]	Nominal bar size [mm] ≤ 8 > 8	± 6,0 ± 4,5		
Bond: Minimum relative rib area, f <sub>R</sub> ,min (determination according to EN 15630)	0,0 0,0			

**Rib height h:** The rib height h must be:  $0.05 \cdot d \le h \le 0.07 \cdot d$ 

fischer injection system FIS V	
Reinforcing bars Installation parameters Materials	Annex 6




Table 6: Installation parameters fischer rebar anchors FRA

Threaded diameter				М	12 <sup>1)</sup>	M 16	M 20	M 24	
Nominal bar size		d	[mm]	1	2	16	20	25	
Nominal drill bit diar	neter	$d_{\scriptscriptstyle{\mathrm{O}}}$	[mm]	(14)	16	20	25	30	
Drill hole depth (	$h_0 = \ell_{e,ges}$ )	$\mathbf{h}_{_{\mathrm{O}}}$	[mm]			h <sub>ef</sub>	+ ℓ <sub>e</sub>		
Effective encharge denth		h <sub>ef,min</sub>	[mm]	7	0	80	90	96	
Lifective afferiorage	Effective anchorage depth		[mm]	14	10	220	300	380	
Distance concrete s to welded join	[mm]	100							
Minimum spacing and s <sub>min</sub> = c <sub>min</sub> [mn				5	55 65 85			105	
	pre-positione anchorage	d d <sub>f</sub>	[mm]	1	4	18	22	26	
	push-through anchorage	d <sub>f</sub>	[mm]		8	22	26	32	
Minimum thickness of concrete member h <sub>min</sub> [min			[mm]	h <sub>o</sub> +30 ≥ 100 h <sub>o</sub> +2d <sub>o</sub>					
Maximum torque moment T <sub>inst,max</sub> [N			[Nm]	4	40 60			150	
Thickness of fixture	minimum		[Nm]			(	)		
THICKHESS OF HIXTURE	maximum	t <sub>fix</sub>	[Nm]			3000			

<sup>1)</sup> Both drill bit diameter can be used

## fischer rebar anchor FRA



Head marking e.g.: FRA (for stainless steel);

FRA C (for high corrosion-resistant steel)

fischer injection system FIS V	
fischer rebar anchor FRA Installation Parameters	Annex 7


<sup>&</sup>lt;sup>2)</sup>For bigger clarance holes in the fixture see chapter 1.1 of the TR 029.

English translation prepared by DIBt




#### Drilling and cleaning the hole

1




Drill the hole. Drill hole diameter  $\mathbf{d}_{\mathrm{o}}$  and drill hole depth  $\mathbf{h}_{\mathrm{o}}$  see Table 1.

2




h<sub>ef</sub>≤ 12d; d<sub>o</sub>< 18mm: Blow out the drill hole four times by hand.



 $h_{ef}$  > 12d;  $d_0 \ge 18$ mm: Blow out the drill hole four times, using oil-free pressure air (p > 6 bar).


3




Brush the drill hole four times using a adequate steel brush and a drill machine. For deep drill holes use an extension.

	8	10	12	14	16	18	20	24	25	28	30	35
d <sub>b</sub> [mm]	9	11	14	16	20	20	25	26	27	30	40	40

4




h<sub>ef</sub>≤ 12d; d<sub>o</sub>< 18mm: Blow out the drill hole four times by hand.



h<sub>ef</sub> > 12d; d<sub>o</sub> ≥ 18mm: Blow out the drill hole four times, using oil-free pressure air (p > 6 bar).


# Preparing the cartridge

5



Twist off the sealing cap.

6



Twist on the mixing nozzle (the spiral in the mixing nozzle must be clearly visible).

7



Place the cartridge into the dispenser.

8





Press out approx. 10 cm of mortar until the resin is permanent grey in colour. Don't use uniformly grey unreal mortar.

fischer injection system FIS V

Installation instructions
Part 1

Annex 8


Z80677.12

English translation prepared by DIBt




#### Injection of the mortar

9




Fill approx. 2/3 of the drill hole with mortar. Always begin from the bottom of the hole to eliminate voids.




For drill hole depth ≥ 150 mm use an extension tube.


#### Installation fischer anchor rods or internal threaded anchors RG MI

|10|






Only use clean and oil-free anchor elements. Mark the anchor element for setting depth. Press the anchor rod or internal threaded anchor down to the bottom of the hole, turning it slightly while doing so. After inserting the anchor element, excess mortar must emerge around the anchor element.



For overhead installation support the anchor rod with wedges.




For push-through installation fill the annular gap with mortar.

11



Wait for the specified curing time. t<sub>cure</sub> see **Table 4**.

12




Mounting the fixture

T<sub>inst,max</sub> see

Table 1 or 2.

### Installation reinforcing bars and fischer rebar anchors FRA

10




Only use clean and oil-free rebars. Mark the reinforcing bar for setting depth. Using a turning movement, push the reinforcing bar or the FRA vigorously into the filled hole up to the insertion depth marking. When reaching the setting depth marking surplus mortar must emerge around the anchor.

11



Wait for the specified curing time. t<sub>cur</sub> see **Table 4**.

12



Mounting the fixture

T<sub>inst,max</sub> see

Table 6.

fischer injection system FIS V

Installation instructions Part 2 Annex 9

Z80677.12



Table 7: Design of Bonded Anchors acc. to TR 029 Characteristic values to tension load for fischer anchor rods

Size				M 6	M 8	M 10	M 12	M 16	M 20	M 24	M 30			
Steel fa	ailure				•									
O ××	Pr	operty	5.8 [kN]	11	19	29	43	79	123	177	281			
risti e N		class	8.8 [kN]	16	30	47	68	126	196	282	449			
cte	stainless _		50 [kN]	11	19	29	43	79	123	177	281			
Characteristic resistance N <sub>RKs</sub>	Steel A4	operty class	70 [kN]	14	26	41	59	110	172	247	393			
<u>ე</u> ნ	and steel C	Class	80 [kN]	16	30	47	68	126	196	282	449			
Pro		operty	5.8 [-]	1,50										
Partial safety factor $\gamma_{_{ m Ms,N}}$		class	8.8 [-]				1,!	50						
alsa r ⅓м	stainless		50 [-]				2,8	36						
steel A4 Pro	operty class	70 [-]				1,50 <sup>3</sup>	/1,87							
- Ψ	and steel C	Class	80 [-]				1,0	<del>5</del> 0						
Combir	ned pullout and	d conc	ete cone	failure										
Diamet	er of calculatio	n	d [mm]	6	8	10	12	16	20	24	30			
	teristic bond r			crete C2	20/25									
	ed use: dry and				I									
	rature range I <sup>4)</sup>			9	11	11	11	10	9,5	9,0	8,5			
Tempe	rature range II <sup>4)</sup>	[N/mm²]	6,5	9,5	9,5	9,0	8,5	8,0	7,5	7,0				
	teristic bond reed use: flooded		ice in con	crete C2	20/25									
Temper	rature range l4)	τ <sub>Rk,ucr</sub>	[N/mm²]	_		_	9,5	8,5	8,0	7,5	7,0			
Tempe	rature range II <sup>4)</sup>	$ au_{ m Rk,ucr}$	[N/mm²]	_	_	_	7,5	7,0	6,5	6,0	6,0			
		C2	5/30 [-]				1,0	D5	•	•				
			0/37 [-]				1,	10						
Increasi			5/45 [-]				1,							
iactors	for $ au_{_{ m RK,ucr}}$ $ extstyle \Psi_{ m c}$		0/50 [-]				1,							
			5/55 [-]				1,2							
Calittia	g failure	C5	0/60 [-]				1,2	26						
opiitun	y ranure	h /	' h <sub>ef</sub> ≥ 2,0				1.0	h						
Edge di	stance						1,0							
C <sub>cr,sp</sub> [m	m] 2		' h <sub>ef</sub> > 1,3				-	- 1,8 h						
		h /	′ h <sub>ef</sub> ≤ 1,3				2,26							
Spacing	9	S	<sub>cr,sp</sub> [mm]				2c <sub>c</sub>	r,sp						
	Partial safety factor dry and wet			1,5 <sup>2)</sup>										
$\gamma_{MP} = \gamma_{M}$	$_{1C} = \gamma_{Msp}^{1)} [-]$	flood	ed hole <sup>6)</sup>		1,8 <sup>5)</sup>									
1\1	ence of other n					a) -	Anney 2							

<sup>1)</sup>In absence of other national regulations

fischer Injections system FIS V Design of Bonded Anchors acc. to TR 029 Annex 10 fischer anchor rods Characteristic values to tension load

<sup>4)</sup>See Annex 2

 $<sup>^{2)}</sup>$  The partial factor  $\gamma_2$  = 1,0 is included  $^{3)}$  For steel C:  $\rm f_{uk}$  = 700 N/mm² ;  $\rm f_{yk}$  = 560 N/mm²

<sup>&</sup>lt;sup>5)</sup>The partial factor  $\gamma_2 = 1.2$  is included

<sup>&</sup>lt;sup>6)</sup>Only for coaxial cartrigde 380ml, 400ml and 410ml



Table 8: Design of Bonded Anchors acc. to TR 029 Characteristic values to shear load fischer anchor rods

		ichiotic vi										
Size				M6	M8	M10	M12	M16	M20	M24	M30	
Steel fail	ure without	lever arm										
. <u>S</u> . <del>Š</del>		Property	5.8 [kN]	5	9	15	21	39	61	89	141	
Characteristic resistance V <sub>Rk.s</sub>		class	8.8 [kN]	8	15	23	34	63	98	141	225	
anc	stainless	Droporty	50 [kN]	5	9	15	21	39	61	89	141	
iara sista	steel A4	Property class	70 [kN]	7	13	20	30	55	86	124	197	
는 월 and steel C	Class	80 [kN]	8	15	23	34	63	98	141	225		
Steel fail	ure with lev	er arm										
.일 占 Pro	Property	5.8[Nm]	8	19	37	65	166	324	561	1124		
Characteristic bending mo- ment M <sup>o</sup> <sub>RK.s</sub>	bending moreistic Characteristic Cha	class	8.8[Nm]	12	30	60	105	266	519	898	1799	
stainless	Property	50[Nm]	8	19	37	65	166	324	561	1124		
and end	Characteris:  Dending ment Mess steel A4 and steel C	class	70[Nm]	11	26	52	92	233	454	785	1574	
3 2 2	and steel C		80[Nm]	12	30	60	105	266	519	898	1799	
Partial sa	afety factor s	steel failu	re									
		Property	5.8 [-]	1,25								
		class	8.8 [-]				1,2	.5				
$\gamma_{Ms,V}^{1}$	stainless	Property	50 [-]				2,3	8				
	steel A4	class	70 [-]				1,25 <sup>3)</sup> /	1,56				
	and steel C		80 [-]				1,3	3				
Concrete	e pryout failu	ire										
Factor k in Equation (5.7) of Technical Report TR 029 k [-] Section 5.2.3.3				2,0								
Partial sa	fety failure		γ <sub>Mcp</sub> <sup>1)</sup> [-]	1,5 <sup>2)</sup>								
Concrete	edge failure	Э		See Technical Report TR 029, Section 5.2.3.4								
Partial sa	fety failure		γ <sub>Mc</sub> 1) [-]				1,5	5 <sup>2)</sup>				
1)												

fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 fischer anchor rods Characteristic values to shear load	Annex 11

 $<sup>^{1)}</sup>$  In absence of other national regulations.  $^{2)}$  The partial safety factor  $\gamma_2 = 1.0$  is included.  $^{3)}$  For steel C:  $f_{uk} = 700 \text{ N/mm}^2$  :  $f_{yk} = 560 \text{ N/mm}^2$ 



Table 9: Displacements of fischer anchor rods to tension load

Size			M6	M8	M10	M12	M16	M20	M24	M30
Temperature range I -40°C / +80°C Effective anchorage depth $h_{ef} = 8 d^{11}$										
Tension load		N [kN]	2,5	7,7	11,0	15,8	25,5	37,9	51,7	76,3
Displacement	$\delta_{_{NO}}$	[mm]	0,1	0,2	0,2	0,2	0,2	0,3	0,3	0,3
Displacement	$\delta_{_{N^{\infty}}}$	[mm]	0,3	0,6	0,6	0,6	0,6	0,9	0,9	0,9
Temperature range I	I -40°C	/+120°C		Effe	ective and	chorage	depth h	$_{\rm sf}$ = 8 d <sup>1)</sup>		
Tension load		N [kN]	2,0	6,4	9,5	12,9	21,7	31,9	43,1	62,8
Displacement	$\delta_{_{NO}}$	[mm]	0,1	0,15	0,15	0,15	0,15	0,25	0,25	0,25
Displacement	$\delta_{_{N\!\infty}}$	[mm]	0,3	0,45	0,45	0,45	0,45	0,75	0,75	0,75

<sup>1)</sup> Values for 8d ≤ h<sub>ef</sub> ≤ 20d can be calculated:

$$\delta_{NO} = \delta_{NO1} \frac{h_{ef}}{8d}$$

$$\delta_{NO1}$$
 for h<sub>ef</sub> 80

$$\delta_{\text{NO}} = \delta_{\text{NO1}} \frac{h_{\text{ef}}}{8d} \qquad \delta_{\text{NO1}} \text{ for } h_{\text{ef}} \text{ 8d} \qquad \qquad \delta_{\text{N} \infty} = \delta_{\text{N} \infty 1} \frac{h_{\text{ef}}}{8d} \qquad \delta_{\text{N} \infty 1} \text{ for } h_{\text{ef}} \text{ 8d}$$

$$\delta_{_{N\!\infty\!1}}$$
 for  $\mathrm{h_{_{ef}}\,8d}$ 

Table 10: Displacements of fischer anchor rods to shear load

Size		M6	M8	M10	M12	M16	M20	M24	M30	
Temperature rang	ge I -40°C / + 80°C	and ten	nperatur	e range	I -40°C	/+120°C	;			
Property class	5.8 / A4-50 / C-50									
Shear load	V [kN]	2,8	5,1	8,1	11,8	21,9	34,2	49,1	78,3	
Displacement	$\delta_{ m vo}$ [mm]	0,7	0,9	1,2	1,4	2,0	2,4	2,6	3,7	
Displacement	$\delta_{_{V\!\infty}}$ [mm]	1,2	1,4	1,7	2,1	2,9	3,7	4,1	5,6	
Property class										
Shear load	V [kN]	3,2	5,9	9,3	13,5	25,2	39,3	56,4	89,9	
Displacement	$\delta_{ m vo}$ [mm]	0,8	1,0	1,3	1,6	2,2	2,8	3,4	4,3	
Displacement	$\delta_{_{V\!\infty}}$ [mm]	1,1	1,6	2,0	2,4	3,4	4,2	5,6	6,4	
Property class	C-70 <sup>1)</sup>									
Shear load	V [kN]	4,0	7,3	11,6	16,9	31,4	49,0	70,4	112,2	
Displacement	$\delta_{ m vo}$ [mm]	1,0	1,3	1,7	2,0	2,8	3,5	4,2	5,3	
Displacement	$\delta_{_{V\!\infty}}$ [mm]	1,4	2,0	2,5	3,0	4,2	5,3	6,3	8,0	
Property class	8.8 / A4-80 / C-80									
Shear load	V [kN]	4,6	7,0	11,1	15,2	30,1	47,0	67,7	107,7	
Displacement	$\delta_{ m vo}$ [mm]	1,0	1,2	1,6	1,9	2,8	3,3	3,6	5,1	
Displacement	$\delta_{_{ m V}\!$	1,6	1,9	2,3	2,9	4,0	5,1	5,6	7,7	

 $<sup>^{1)}</sup>f_{uk} = 700 \text{ N/mm}^2 : f_{yk} = 560 \text{ N/mm}^2$ 

fischer injection system FIS V	
fischer anchor rods Displacements	Annex 12



Table 11: Design of Bonded Anchors acc. to TR 029 Characteristic values to tension load for fischer internal threaded anchors RG MI

Size				M 8	M 10	M 12	M 16	M 20				
Steel failure												
Chanastanistis		Property-	5.8 [kN]	19	29	43	79	123				
Characteristic resitance	N	class	8.8 [kN]	29	47	68	108	179				
with screw	$N_{Rk,s}$	Property-	A4 [kN]	26	41	59	110	172				
vvitir screvv		class 70	C [kN]	26	41	59	110	172				
		Property-		1,50								
Partial safety	$\gamma_{Ms,N}^{-1)}$	class	8.8 [-]			1,50						
factor	* IVIS,IN	Property-	A4 [-]			1,87						
		class 70	C [-]			1,87						
Combined pullout an		failure			T							
Diameter for calculati			d <sub>H</sub> [mm]	12	16	18	22	28				
Effective anchorage d			h <sub>ef</sub> [mm]	90	90	125	160	200				
Characteristic values Intended use: dry an												
Temperature range I (	-40°C/+80	°C) <sup>3)</sup> I	$N_{Rk,p}^{0}$ [kN]	30	40	50	75	115				
Temperature range II	(-40°C/+12		N <sub>Bk,p</sub> [kN]	25	30	40	60	95				
Characteristic values Intended use: floode								•				
Temperature range I (	-40°C/+80	°C) <sup>3)</sup> I	$N_{Rk,p}^{O}$ [kN]	25	35	50	60	95				
Temperature range II	(-40°C/+12	20°C) <sup>3)</sup>	N <sub>Rk,p</sub> [kN]	20	25	35	50	75				
			C25/30 [-]		•	1,05		•				
			C30/37 [-]			1,10						
Increasing factors for	$N_{Bk,p}^{O}$	$\Psi_{c}$	C35/45 [-]			1,15						
		Ψ <sub>C</sub>	C40/50 [-]			1,19						
			C45/55 [-]			1,22						
			C50/60 [-]	1,26								
Splitting failure												
		_	h / h <sub>ef</sub> ≥ 2,0			1,0 h <sub>ef</sub>						
Edge distance c <sub>cr,sp</sub> [	mm]	2,0 >	h / h <sub>ef</sub> > 1,3	4,6 h <sub>ef</sub> - 1,8 h								
			h / h <sub>ef</sub> ≤ 1,3	2,26 h <sub>ef</sub>								
Spacing			s <sub>cr,sp</sub> [mm]	2c <sub>cr,sp</sub>								
Partial safety factor dry and we				1,5 <sup>2)</sup>								
$\gamma_{Mp} = \gamma_{Mc} = \gamma_{Msp}^{1}  [-]$			oded hole <sup>5)</sup>			1,8 4)						

<sup>&</sup>lt;sup>1)</sup>In absence of other national regulations

 $<sup>^{4)}</sup>$  The partial factor  $\gamma_2$  =1,2 is included  $^{5)}$  Only for coaxial cartrigde 380ml, 400ml and 410ml

fischer injection system FIS V							
Design of Bonded Anchors acc. to TR 029 fischer internal threaded anchors RG MI Characteristic values to tension load	Annex 13						

8.06.01-237/12 Z80677.12

<sup>&</sup>lt;sup>2)</sup>The partial factor  $\gamma_2 = 1.0$  is included

<sup>3)</sup>See Annex 2



**Table 12:** Design of Bonded Anchors acc. to TR 029 Characteristic values to shear load for fischer internal threaded anchors RG MI

Size				M 8	M 10	M 12	M 16	M 20
Steel failure without le	ever arm							0
		Property	5.8 [kN]	9,2	14,5	21,1	39,2	62
Characteristic	\/	class	8.8 [kN]	14,6	23,2	33,7	62,7	90
resistance	$V_{Rk,s}$	Property	A4 [kN]	12,8	20,3	29,5	54,8	86
		class 70	C [kN]	12,8	20,3	29,5	54,8	86
		Property	5.8 [-]			1,25		
Partial safety factor	$\gamma_{Ms,V}$	class	8.8 [-]		1,:	25		1,5
raitial safety factor	• IVIs,V	Property	A4 [-]			1,56		
		class 70	C [-]			1,56		
Steel failure with leve	r arm							
Characteristic		Property	5.8[Nm]	20	39	68	173	337
	$M^O_Rk,s$	class	8.8[Nm]	30	60	105	266	519
bending moment	IVI <sub>Rk,s</sub>	Property	A4[Nm]	26	52	92	232	454
		class 70	C[Nm]	26	52	92	232	454
		Property	5.8 [-]			1,25		
Partial safety factor	$\gamma_{Ms,V}$	class				1,25		
Tartial salety lactor	• IVIS, V	Property	A4 [-]			1,56		
		class 70	C [-]			1,56		
Concrete pryout failur	е							
Factor k in Equation (5. Report TR 029, Section	•	cal	k [-]			2,0		
Partial safety factor			γ <sub>Mcp</sub> 1) [-]			1,52)		
Concrete edge failure				See Ted	chnical Rep	ort TR 029	, Section 5	5.2.3.4
Partial safety factor			γ <sub>Mc</sub> 1) [-]			1,52)		

<sup>1)</sup> In absence of other national regulations.

fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 fischer internal threaded anchors RG MI Characteristic values to shear load	Annex 14

 $<sup>^{2)}\,\</sup>text{The partial safety factor}\,\gamma_2$  = 1,0 is included.



Table 13: Displacement of internal threaded anchors RG MI to tension load

Size			M8	M10	M12	M16	M20				
Temperature range I (-40°C / + 80°C)											
Tension load		N [kN]	11,9	13,8	19,8	29,8	69,4				
Displacement	$\delta_{_{ m NO}}$	[mm]	0,2	0,2	0,3	0,3	0,7				
Displacement	$\delta_{_{N\!\infty}}$	[mm]	0,6	0,6	0,9	0,9	2,1				
Temperature range	II (-40°C	/ + 120°C)									
Tension load		N [kN]	9,9	11,9	15,8	23,8	37,7				
Displacement	$\delta_{_{NO}}$	[mm]	0,15	0,15	0,25	0,25	0,6				
Displacement	$\delta_{_{N^{\infty}}}$	[mm]	0,45	0,45	0,75	0,75	1,8				

Table 14: Displacement of internal threaded anchors RG MI to shear load

Size		M8	M10	M12	M16	M20			
Temperature range I -40°C / + 80°C and temperature range II -40°C / +120°C									
Shear load (property class 5.8)	V [kN]	5,1	8,1	11,8	21,9	34,2			
Displacement $\delta_{_{ m VO}}$	[mm]	0,9	1,2	1,4	2,0	2,4			
Displacement $\delta_{_{_{\!$	[mm]	1,4	1,7	2,1	2,9	3,7			
Shear load (property class 8.8)	V [kN]	7,0	11,1	16,2	30,1	47,0			
Displacement $\delta_{_{ extsf{VO}}}$	[mm]	1,2	1,6	1,9	2,8	3,3			
Displacement $\delta_{_{\!$	[mm]	1,9	2,3	2,9	4,0	5,1			
Shear load (property class A4-7	0) V [kN]	5,9	9,3	13,5	25,2	39,3			
Displacement $\delta_{_{ m VO}}$	[mm]	1,0	1,3	1,6	2,2	2,8			
Displacement $\delta_{_{_{\!$	[mm]	1,6	2,0	2,4	3,4	4,2			
Shear load (property class C 70	1) V [kN]	7,3	11,6	16,9	31,4	49,0			
Displacement $\delta_{ m vo}$	[mm]	1,3	1,7	2,0	2,8	3,5			
Displacement $\delta_{_{ extsf{V}\!\infty}}$	[mm]	2,0	2,5	3,0	4,2	5,3			

 $<sup>^{1)}</sup>f_{uk} = 700 \text{ N/mm}^2$ ;  $f_{yk} = 560 \text{ N/mm}^2$ 

fischer injection system FIS V	
fischer internal threaded anchors RG MI Displacements	Annex 15



Table 15: Design of Bonded Anchors acc. to TR 029
Characteristic values to tension load for reinforcing bars 4)

Size		Ød	8	10	12	14	16	20	25	28	
Steel failure					_						
Characteristic resistance		N <sub>Rk,s</sub> [kN]	28	44	63	85	111	173	270	339	
Partial safety factor		$\gamma_{Ms,N}^{-1}$ [-]				1,	.4				
Combined pullout and	l cor										
Diameter for calculation	n	d [mm]	8	10	12	14	16	20	25	28	
Characteristic bond re	esist	ance in conc	rete C20	0/25							
Temperature range I <sup>3)</sup> (-40°C/+80°C)	$\tau_{_{\mathrm{RI}}}$	κ,ucr [N/mm²]	11,0	11,0	11,0	10,0	10,0	9,5	9,0	8,5	
Temperature range II <sup>3)</sup> (-40°C/+120°C)	$\tau_{_{\mathrm{RI}}}$	<sub>c,ucr</sub> [N/mm²]	9,5	9,5	9,0	8,5	8,5	8,0	7,5	7,0	
		C25/30 [-]	1,05								
		C30/37 [-]	1,10								
Increasing factor	Ψ <sub>c</sub> .	C35/45 [-]		1,15							
for τ <sub>Rk,ucr</sub>	С.	C40/50 [-]	1,19								
		C45/55 [-]					22				
		C50/60 [-]				1,	26				
Splitting failure											
		h / h <sub>ef</sub> ≥ 2,0				1,0	) h <sub>ef</sub>				
Edge distance c <sub>crsp</sub> [mm] 2,0		h / h <sub>ef</sub> >1,3				4,6 h	- 1,8 h				
		h / h <sub>ef</sub> ≤1,3				2,2	6 h <sub>ef</sub>				
Spacing		s <sub>cr,sp</sub> [mm]				2 (	C <sub>cr,sp</sub>				
Partial safety γ, factor	м <sub>р</sub> = ?	$\gamma_{Mc} = \gamma_{Msp}^{1)} [-]$					5 <sup>2)</sup>				

<sup>1)</sup> In absence of other national regulations.

510.14	
fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 Reinforcing bars	Annex 16
Characteristic values to tension load	

<sup>&</sup>lt;sup>2)</sup>The partial safety factor  $\gamma_2 = 1.0$  is included

<sup>3)</sup> See Annex 2

<sup>&</sup>lt;sup>4)</sup>The values given in Table 15 are valid for reinforcing bars B 500 B with  $f_{uk}$  = 550 N/mm<sup>2</sup> and  $f_{yk}$  = 500 N/mm<sup>2</sup>. Other reinforcing bars have to be calculated according to TR 029, Equation (5.1).



**Table 16:** Design of Bonded Anchors acc. to TR 029
Characteristic values to shear load for reinforcing bars<sup>1)</sup>

Size Ø d	8	10	12	14	16	20	25	28	
Steel failure without I	ever arm								
Characteristic $V_{Rk,s}$ [kN] resistance	13,8	21,6	31,1	42,4	55,3	87	135	170	
Partial safety $\gamma_{\rm Ms,V}$ [-]		1,5							
Steel failure with leve	r arm								
Characte- ristic M <sub>Rk,s</sub> [Nm] bending moment	33	65	112	178	265	518	1012	1422	
Partial safety $\gamma_{\rm Ms,V}$ [-]		1,5							
Concrete pryout failur	re								
Factor k in Equation (5.7) of Technical Report TR 029, k[-] Section 5.2.3.3				2,	0				
Partial safety $\gamma_{\rm Mcp}^{~~2)}$ [-]		1,5 <sup>3)</sup>							
Concrete edge failure		See	Technical	Report TF	R 029, Sed	ction 5.2.3	3.4		
Partial safety $\gamma_{Mc}^{-2)}$ [-]				1,!	5 <sup>3)</sup>				

The values given in Table 16 are valid for reinforcing bars B 500 B with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{yk} = 500 \text{ N/mm}$ .

Other reinforcing bars have to be calculated according to TR 029, Equation (5.1).

fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 Reinforcing bars Characteristic values to shear load	Annex 17

<sup>&</sup>lt;sup>2)</sup> In absence of other national regulations.

 $<sup>^{\</sup>rm 3)}$  The partial safety factor  $\gamma_2$  = 1.0 is included.

English translation prepared by DIBt



Table 17: Displacements of reinforcing bars to tension load 1)

Size		Ød	8	10	12	14	16	20	25	28
Temperature range I -40°C / +80°C Effective anchorage depth $h_{ef} = 8 d^{2}$										
Tension load		N [kN]	7,7	11,0	15,8	19,5	25,5	37,9	51,7	76,3
Displacement	$\delta_{_{ m NO}}$	[mm]	0,2	0,2	0,2	0,2	0,2	0,3	0,3	0,3
Displacement	$\delta_{_{N\infty}}$	[mm]	0,6	0,6	0,6	0,6	0,6	0,9	0,9	0,9
Temperature range	II -40°C	/+120°C		Effe	ective an	chorage	depth h <sub>e</sub>	$= 8 d^{2}$		
Tension load		N [kN]	6,4	9,5	12,9	16,6	21,7	31,9	43,1	62,8
Displacement	$\delta_{_{ m NO}}$	[mm]	0,15	0,15	0,15	0,15	0,15	0,25	0,25	0,25
Displacement	$\delta_{N\infty}$	[mm]	0,45	0,45	0,45	0,45	0,45	0,75	0,75	0,75

The values given in Table 17 are valid for reinforcing bars B 500 B with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{yk} = 500 \text{ N/mm}^2$ . Other reinforcing bars have to be calculated according to TR 029, Equation (5.1).

Values for 8d ≤ h<sub>ef</sub> ≤ 20d can be calculated:

$$\delta_{NO} = \delta_{NO1} \frac{h_{ef}}{8d} \qquad \delta_{NO1} \text{ for } h_{ef} 8d$$

$$\delta_{N\infty} = \delta_{N\infty 1} \frac{h_{ef}}{8d} \delta_{N\infty 1} \text{ for } h_{ef} 8d$$

Tabelle 18: Displacements of reinforcing bars to shear load 1)

Size		Ød	8	10	12	14	16	20	25	28
Temperature range I -40°C / + 80°C and temperature range II -40°C /+120°C										
Shear load		V [kN]	5,1	8,1	11,8	16,0	21,9	34,2	49,1	78,3
Displacement	$\delta_{VO}$	[mm]	0,9	1,2	1,4	0,7	2,0	2,4	2,6	3,7
Displacement	$\delta_{_{V^{\infty}}}$	[mm]	1,4	1,7	2,1	1,2	2,9	3,7	4,1	5,6

The values given in Table 18 are valid for reinforcement bars B 500 B with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{yk} = 500 \text{ N/mm}^2$ . Other reinforcing bars have to be calculated according to TR 029, Equation (5.1).

fischer injection system FIS V

Reinforcing bars
Displacements

Annex 18



**Table 19:** Design of Bonded Anchors acc. to TR 029

Characteristic values to tension load for fischer rebar anchors FRA

Size		M12	M16	M20	M24			
Steel failure								
Characteristic resistance	N <sub>Rk,s</sub> [kN]	63	111	173	270			
Partial safety factor	$\gamma_{Ms,N}^{1)}$ [-]							
Combined pullout and concrete	e failure							
Diameter of calculation	d [mm]	12	16	20	25			
Characteristic bond resistance	in concrete C20/25							
Temperature range I <sup>3)</sup> (-40°C / +80°C)	τ <sub>Rk.ucr</sub> [N/mm²]	11,0	10,0	9,5	9,0			
Temperature range II <sup>3)</sup> (-40°C /+120°C)	τ <sub>Rk,ucr</sub> [N/mm²]	9,0	8,5	8,0	7,5			
	C25/30 [-]	1,05						
	C30/37 [-]	10						
Increasing factors	C35/45 [-]	1,15						
for $\tau_{\rm Rk,ucr}$	C40/50 [-]		1,1					
	C45/55 [-]		1,2					
	C50/60 [-]		1,2	26				
Splitting failure								
	h / h <sub>ef</sub> ≥ 2,0		1,0	) h <sub>ef</sub>				
Edge distance c <sub>cr,sp</sub> [mm]	2,0 > h / h <sub>ef</sub> > 1,3	4,6 h <sub>ef</sub> - 1,8 h						
	h / h <sub>ef</sub> ≤ 1,3			6 h <sub>ef</sub>				
Spacing	S <sub>cr,sp</sub> [mm]		2 c	cr.sp				
Partial safety factor	$\gamma_{Mp} = \gamma_{Mc} = \gamma_{Msp}^{1}$ [-]		1,!	5 <sup>2)</sup>				

<sup>1)</sup> In absence of other national regulations.

fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 fischer rebar anchor FRA Characteristic values to tension load	Annex 19

 $<sup>^{2)}</sup>$  The partial safety factor  $\gamma_{2}$  = 1,0 is included

<sup>3)</sup> See Annex 2

English translation prepared by DIBt



**Table 20:** Design of Bonded Anchors acc. to TR 029
Characteristic values to shear load for fischer rebar anchors FRA

Size		M12	M16	M20	M24	
Steel failure without lever arm						
Characteristic resistance	$V_{Rk,s}$ [kN]	30	55	86	124	
Partial safety factor	γ <sub>Ms,V</sub> [-]		1,!	56		
Steel failure with lever arm						
Characteristic bending moment	$M_{Rk,s}^{0}$ [Nm]	92	233	454	785	
Partial safety factor	γ <sub>Ms,V</sub> [-]	1,56				
Concrete pryout failure						
Factor k in Equation (5.7) of Technical Report TR 029, Section 5.2.3.3	k [-]		2	,0		
Partial safety factor	γ <sub>Mcp</sub> [-]		1,	5 <sup>2)</sup>		
Concrete edge failure		See Tech	nnical Report T	R 029, Section	n 5.2.3.4	
Partial safety factor	γ <sub>Mc</sub> [-]		1,	5 <sup>2)</sup>		

<sup>1)</sup> In absence of other national regulations.

fischer injection system FIS V	
Design of Bonded Anchors acc. to TR 029 fischer rebar anchor FRA Characteristic values to shear load	Annex 20

 $<sup>^{2)}</sup>$  The partial safety factor  $\,\gamma_{2}^{}=$  1,0 is included.



Table 21: Displacements of fischer rebar anchors FRA to tension load

Size			M12	M16	M20	M24		
Temperature range	1 -40°C	/ +80°C	Effectiv	ve anchorage de	$epth h_{ef} = 8 d^{1}$			
Tension load		N [kN]	15,8	25,5	37,9	51,7		
Displacement	$\delta_{_{NO}}$	[mm]	0,2	0,2	0,3	0,3		
Displacement	$\delta_{_{N^{\infty}}}$	[mm]	•	0,6	0,9	0,9		
Temperature range	II -40°C	/+120°C	Effective anchorage depth h <sub>ef</sub> = 8 d <sup>1)</sup>					
Tension load		N [kN]	12,9	21,7	31,9	43,1		
Displacement	$\delta_{_{NO}}$	[mm]	0,15	0,15	0,25	0,25		
Displacement	$\delta_{_{N\infty}}$	[mm]	0,45	0,45	0,75	0,75		

<sup>1)</sup> Values for 8d ≤ h<sub>ef</sub> ≤ 20d can be calculated:

$$\delta_{\text{NO}} = \delta_{\text{NO1}} \frac{h_{\text{ef}}}{8d}$$
  $\delta_{\text{NO1}}$  for  $h_{\text{ef}}$  8d

$$\delta_{\rm N\infty} = \delta_{\rm N\infty 1} \frac{h_{\rm ef}}{8d} \delta_{\rm N\infty 1} \text{ for } h_{\rm ef} 8d$$

Table 22: Displacements of fischer rebar anchors FRA to shear load

Size			M12	M16	M20	M24			
Temperature range I -40°C /+ 80°C and temperature range II -40°C /+120°C									
Shear load		V [kN]	11,8	21,9	34,2	49,1			
Displacement	$\delta_{vo}$	[mm]	1,4	2,0	2,4	2,6			
Displacement	$\delta_{_{V^{\infty}}}$	[mm]	2,1	2,9	3,7	4,1			

fischer injection system FIS V

fischer rebar anchor FRA
Displacements

Annex 21



**Table 23:** Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Characteristic values to tension load for fischer anchor rods

Size				M 6	M 8	M 10	M 12	M 16	M 20	M 24	M 30	
Steel fa	ailure				_							
ပ နို	Pr	operty	5.8 [kN]	11	19	29	43	79	123	177	281	
Characteristic resistance N <sub>RK.s</sub>		class	8.8 [kN]	16	30	47	68	126	196	282	449	
anc	stainless <sub>D</sub>		50 [kN]	11	19	29	43	79	123	177	281	
nara sist	Steel A4	operty class	70 [kN]	14	26	41	59	110	172	247	393	
<u>ئ</u> ء	and steel C	Oldoo	80 [kN]	16	30	47	68	126	196	282	449	
>	Pr	operty	5.8 [-]				1,!	50				
Partial safety factor $\gamma_{_{Ms,N}}^{}$		class	8.8 [-]				1,5	50				
als. r. <sup>≻</sup> √	stainless		50 [-]				2,8	36				
arti acto	steel A4	operty class	70 [-]		1,50 <sup>3</sup> /1,87							
T 42	and steel C	Class	80 [-]				1,6	30				
Combi	ned pullout an	d concr	ete cone	failure								
Diamet	ter of calculatio	n	d [mm]	6	8	10	12	16	20	24	30	
Charac	teristic bond r	esistan	ice in con	crete C2	0/25. In	tended u	se: dry a	nd wet c	oncrete			
Tempe	rature range l <sup>4)</sup>	9	11	11	11	10	9,5	9,0	8,5			
Tempe	rature range II <sup>4</sup>	τ <sub>Bkucr</sub>	[N/mm²]	6,5	9,5	9,5	9,0	8,5	8,0	7,5	7,0	
Charac	teristic bond r	esistan	ice in con	crete C2	.0/25. In	tended u	se: flood	ed hole <sup>6)</sup>				
	rature range I <sup>4)</sup>			_		_	9,5	8,5	8,0	7,5	7,0	
Tempe	rature range II <sup>4</sup>	<sup>)</sup> τ <sub>Rk,ucr</sub>	[N/mm²]	_		_	7,5	7,0	6,5	6,0	6,0	
Factor	for uncracked o	concrete	e k <sub>ucr</sub> [-]	10,1								
			5/30 [-]				1,0	D5				
lasusos	:		0/37 [-]				1,					
Increas factors	for $ au_{_{RK,ucr}}$		5/45 [-]				1,					
	RK,ucr		0/50 [-] 5/55 [-]				1,1 1,2					
			0/60 [-]				1,2					
Splittin	ng failure		0,00 []				-,-					
•		h /	h <sub>ef</sub> ≥ 2,0				1,0	h <sub>of</sub>				
Edge di C <sub>cr,sp</sub> [m			h <sub>ef</sub> > 1,3					- 1,8 h				
ci,sp =		h /	′ h <sub>ef</sub> ≤ 1,3				2,26	h <sub>ef</sub>				
Spacino	g	s	cr,sp [mm]				2c	r,sp				
	safety factor	dry	and wet									
$\gamma_{MP} = \gamma_{N}$	$_{MC} = \gamma_{Msp}^{1)} [-]$	flood	ed hole <sup>6)</sup>	1,8 <sup>5)</sup>								
	ence of other na	tional re	egulations			5)The i	nartial fac	tor v = 1	2 is includ	ed		

<sup>1)</sup>In absence of other national regulations

Displacements see Annex 12

fischer Injections system FIS V

Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 fischer anchor rods
Characteristic values to tension load

Annex 22

<sup>&</sup>lt;sup>2)</sup>The partial factor  $\gamma_2 = 1.0$  is included

 $<sup>^{3)}\!</sup>For\,steel\,C;\,f_{uk}^{}=700\;N/mm^2$  ;  $f_{yk}^{}=560\;N/mm^2$ 

<sup>&</sup>lt;sup>4)</sup>See Annex 2

<sup>&</sup>lt;sup>5)</sup>The partial factor  $\gamma_2 = 1.2$  is included

<sup>&</sup>lt;sup>6)</sup>Only for coaxial cartrigde 380ml, 400ml and 410ml



Table 24: Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Characteristic values to shear load for fischer anchor rods

Size				М6	M8	M10	M12	M16	M20	M24	M30
Steel fail	ure without	lever arm									
R,s ii		Property	5.8 [kN]	5	9	15	21	39	61	89	141
e V	Characteristic resistance V <sub>RKs</sub> and steel C but he seems that the	class	8.8 [kN]	8	15	23	34	63	98	141	225
stainless	Droporty	50 [kN]	5	9	15	21	39	61	89	141	
iara sista	steel A4	Property class	70 [kN]	7	13	20	30	55	86	124	197
년 ñ	and steel C	Class	80 [kN]	8	15	23	34	63	98	141	225
Steel fail	ure with lev	er arm									
ا <del>إ</del> ذ		Property		8	19	37	65	166	324	561	1124
Characteristic bending mo- ment M <sup>o</sup> <sub>Rks</sub>		class	8.8[Nm]	12	30	60	105	266	519	898	1799
ing F M	stainless		50[Nm]	8	19	37	65	166	324	561	1124
Characteris bending m ment M <sup>o</sup> <sub>k,s</sub>	steel A4	class	70[Nm]	11	26	52	92	233	454	785	1574
3 2 2	and steel C	Clubb	80[Nm]	12	30	60	105	266	519	898	1799
Ductility f	actor		k <sub>2</sub> [-]	0,8							
Partial sa	fety factor s	steel failui	e								
		Property	5.8 [-]	1,25							
		class	8.8 [-]				1,:	25			
γ <sub>Ms,V</sub> 1)	stainless	Property	50 [-]				2,3	38			
	steel A4	class	70 [-]				1,25 <sup>3)</sup>	/ 1,56			
	and steel C	0,000	80 [-]				1,:	33			
Concrete	pryout failu	re									
Factor in Equation (5.7) of CEN/TS 1992-4-4 k <sub>3</sub> [-] Section 6.3.3			k <sub>3</sub> [-]	2,0							
Partial saf	fety failure		γ <sub>Mcp</sub> 1) [-]	1,5 <sup>2</sup>							
Concrete	edge failure	)		See CEN/TS 1992-4: Section 6.3.4							
Partial saf	fety failure		γ <sub>Mc</sub> [-]				1,	5 <sup>2)</sup>			

<sup>1)</sup> In absence of other national regulations.

Displacements see Annex 12.

fischer injection system FIS V	
Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 fischer anchor rods Characteristic values to shear load	Annex 23

The partial safety factor  $\gamma_2 = 1.0$  is included. For steel C:  $f_{uk} = 700 \text{ N/mm}^2$   $f_{yk} = 560 \text{ N/mm}^2$ 



**Table 25**: Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009

Characteristic values to tension load for fischer internal threaded anchors RG MI

Size				M 8	M 10	M 12	M 16	M 20		
Steel failure				•	•					
Characteristic		Property-	5.8 [kN]	19	29	43	79	123		
Characteristic resitance	N	class	8.8 [kN]	29	47	68	108	179		
with screw	$N_{Rk,s}$	Property-	A4 [kN]	26	41	59	110	172		
		class 70	C [kN]	26	41	59	110	172		
		Property-				1,50				
Partial safety	$\gamma_{Ms,N}^{-1)}$	class	8.8 [-]			1,50				
factor	· IVIS,IN	Property-	A4 [-]			1,87				
<u> </u>		class 70	C [-]			1,87				
Combined pullout and		tailure	al F 1	10	10	10	I 00	00		
Diameter for calculation			d <sub>H</sub> [mm]	12	16	18	22	28		
Effective anchorage de			h <sub>ef</sub> [mm]	90	90	125	160	200		
Characteristic values i	n concret	e C20/25.	Intended us	e: dry and	wet concre	ete				
Temperature range I (-4	$V_{Rk,p}^{O}$ [kN]	30	40	50	75	115				
Temperature range II (-	40°C/+12	(O°C) <sup>3)</sup> I	$V_{Rk,p}^{O}$ [kN]	25	30	40	60	95		
Characteristic values i	n concret	e C20/25.	Intended us	e: flooded	hole <sup>5)</sup>					
Temperature range I (-4	10°C/+80	°C) <sup>3)</sup> I	$V_{Rk,p}^{O}$ [kN]	25	35	50	60	95		
Temperature range II (-	40°C/+12	(O°C)3)	$V_{Rk,p}^{O}$ [kN]	20	25	35	50	75		
Factor for uncracked co	ncrete		k <sub>ucr</sub> [-]	10,1						
			C25/30 [-]			1,05				
			C30/37 [-]	1,10						
Increasing factors for N	O Rk,p	$\Psi_{\mathrm{c}}$	C35/45 [-]		1,15					
	•		C40/50 [-]			1,19				
			C45/55 [-]		1,22					
			C50/60 [-]		1,26					
Splitting failure										
		_	h / h <sub>ef</sub> ≥ 2,0			1,0 h <sub>ef</sub>				
Edge distance c <sub>cr,sp</sub> [m	nm]	2,0 >	h / h <sub>ef</sub> > 1,3			4,6 h <sub>ef</sub> - 1,	8 h			
			h / h <sub>ef</sub> ≤ 1,3	2,26 h <sub>ef</sub>						
Spacing			s <sub>cr,sp</sub> [mm]	2c <sub>cr.sp</sub>						
Partial safety factor			dry and wet		1,5 <sup>2)</sup>					
$\gamma_{Mp} = \gamma_{Mc} = \gamma_{Msp}^{1)}  [-]$		flo	oded hole <sup>5)</sup>			1,8 4)				

<sup>&</sup>lt;sup>1)</sup>In absence of other national regulations

Displacements see 15

fischer injection system FIS V

Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 fischer internal threaded anchors RG MI Characteristic values to tension load

Annex 24

<sup>&</sup>lt;sup>2)</sup>The partial factor  $\gamma_2 = 1.0$  is included

<sup>3)</sup>See Annex 2

<sup>&</sup>lt;sup>4)</sup>The partial factor  $\gamma_2 = 1.2$  is included

<sup>&</sup>lt;sup>5)</sup>Only for coaxial cartrigde 380ml, 400ml and 410ml



**Table 26**: Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009
Characteristic values to shear load for fischer internal threaded anchors RG MI

Size	· ·	·		M 8	M 10	M 12	M 16	M 20
Steel failure without le	ever arm		'					
		Property	5.8 [kN]	9,2	14,5	21,1	39,2	62
Characteristic	V	class	8.8 [kN]	14,6	23,2	33,7	62,7	90
resistance	V <sub>Rk,s</sub>	Property	A4 [kN]	12,8	20,3	29,5	54,8	86
		class 70	C [kN]	12,8	20,3	29,5	54,8	86
		Property	5.8 [-]			1,25		
Partial safety factor	$\gamma_{Ms.V}$	class	0.0		1,:	25		1,5
Tartial safety factor	· IVIS, V	Property	A4 [-]			1,56		
		class 70	C [-]			1,56		
Steel failure with lever	r arm							
Characteristic		Property	5.8[Nm]	20	39	68	173	337
	$M^O_{Rk,s}$	class	8.8[Nm]	30	60	105	266	519
bending moment	IVI <sub>Rk,s</sub>	Property	A4[Nm]	26	52	92	232	454
		class 70	C[Nm]	26	52	92	232	454
Ductility factor			k <sub>2</sub> [-]	0,8				
		Property	5.8 [-]					
Partial safety factor	$\gamma_{Ms,V}$	class				1,25		
rartial salety lastor	• IVIS,V	Property				1,56		
		class 70	C [-]			1,56		
Concrete pryout failure	е							
Factor in Equation (27)			k <sub>2</sub> [-]			2,0		
CEN/TS 1992-4-4, Sec	tion 6.3.3		3	2,0				
Partial safety factor		1	Y <sub>Mcp</sub> <sup>1)</sup> [-]	1,5 <sup>2)</sup>				
Concrete edge failure				See CEN/TS 1992-4; Section 6.3.4				
Partial safety factor			γ <sub>Mc</sub> [-]			1,52)		

<sup>1)</sup> In absence of other national regulations.

Displacements see annex 15.

fischer injection system FIS V	
Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 fischer internal threaded anchors RG MI Characteristic values to shear load	Annex 25

 $<sup>^{2)}\,</sup> The$  partial safety factor  $\gamma_2$  = 1,0 is included.



**Table 27:** Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Characteristic values to tension load for reinforcing bars <sup>4)</sup>

Size	Ød	8	10	12	14	16	20	25	28
Steel failure						'		'	
Characteristic resistance	N <sub>Rk,s</sub> [kN]	28	44	63	85	111	173	270	339
Partial safety factor				1.	,4				
Combined pullout and	concrete failure								
Diameter for calculation	d [mm]	8	10	12	14	16	20	25	28
Characteristic bond res	sistance in conc	rete C20	0/25						
Temperature range I <sup>3)</sup> (-40°C/+80°C)	τ <sub>Rk,ucr</sub> [N/mm²]	11,0	11,0	11,0	10,0	10,0	9,5	9,0	8,5
Temperature range II <sup>3)</sup> (-40°C/+120°C)	τ <sub>Rk,ucr</sub> [N/mm²]	9,5	9,5	9,0	8,5	8,5	8,0	7,5	7,0
Factor for uncracked cor	ncrete k <sub>ucr</sub> [-]				10	0,1			
	C25/30 [-]	1,05							
	C30/37 [-]	1,10							
Increasing factor	C35/45 [-]					15			
for $\tau_{\rm Rk,ucr}$	C40/50 [-]				1,	19			
	C45/55 [-]					22			
	C50/60 [-]	1,26							
Splitting failure									
	h / h <sub>ef</sub> ≥ 2,0				1,0	) h <sub>ef</sub>			
Edge distance c <sub>cr.sp</sub> [mm] 2,	0 > h / h <sub>ef</sub> >1,3	4,6 h <sub>ef</sub> - 1,8 h							
	h / h <sub>ef</sub> ≤1,3	2,26 h <sub>ef</sub>							
Spacing	s <sub>cr,sp</sub> [mm]				2 (	C <sub>cr,sp</sub>			
Partial safety $\gamma_{\rm M}$ factor	$_{\rm p}$ = $\gamma_{\rm Mc}$ = $\gamma_{\rm Msp}^{-1}$ [-]					5 <sup>2)</sup>			

<sup>1)</sup> In absence of other national regulations.

$$N_{Rk,s} = A_s \cdot f_{uk}[N]$$

$$\gamma_{Ms} = \frac{1.2}{f_{yk} / f_{uk}} \ge 1.4$$

Displacements see Annex 18.

fischer injection system FIS V	
Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Reinforcing bars Characteristic values to tension load	Annex 26

<sup>&</sup>lt;sup>2)</sup>The partial safety factor  $\gamma_2 = 1.0$  is included

<sup>3)</sup> See Annex 2

<sup>4)</sup> The values given in Table 27 are valid for reinforcing bars B 500 B with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{yk} = 500 \text{ N/mm}^2$ . Other reinforcing bars have to be calculated according to aquation:



Table 28: Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Characteristic values to shear load for reinforcing bars <sup>1)</sup>

Size Ø d	8	10	12	14	16	20	25	28
Steel failure without lever arm								
Characteristic $V_{Rk,s}$ [kN] resistance	13,8	21,6	31,1	42,4	55,3	87	135	170
Partial safety $$\gamma_{\rm Ms,V}$$ [-]	1,5							
Steel failure with lever a	ırm							
Characte- ristic M <sub>Rk,s</sub> [Nm] bending moment	33	65	112	178	265	518	1012	1422
Ductility factor k <sub>2</sub> [-]	0,8							
Partial safety $\gamma_{\text{Ms,V}}$ [-]	1,5							
Concrete pryout failure								
Factor in Equation (27) CEN/TS 1992-4-4 k <sub>3</sub> [-] Section 6.3.3	2,0							
Partial safety γ <sub>Mcp</sub> [-]	<b>1</b> ,5 <sup>3)</sup>							
Concrete edge failure	See CEN/TS 1992-4, Section 6.3.4							
Partial safety $\gamma_{\rm Mc}^{-2}$ [-]	1,5 <sup>3)</sup>							

<sup>&</sup>lt;sup>1)</sup>The values given in Table 28 are valid for reinforcing bars B 500 B with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{yk} = 500 \text{ N/mm}^2$ . Other reinforcing bars have to be calculated according to aquation:

$$\begin{split} V_{Rk,s} &= 0.5 \, \bullet \, A_s \, \bullet \, f_{uk} \, [N] \\ \gamma_{Ms} &= \frac{1.0}{f_{yk} \, / \, f_{uk}} \, \ge \, 1.25 \qquad \text{for} \ \ f_{uk} \le 800 \, \text{N/mm}^2 \ \ \text{and} \ \ f_{yk} / f_{uk} \le 0.8 \\ \gamma_{Ms} &= 1.5 \qquad \qquad \text{for} \ \ f_{uk} > 800 \, \text{N/mm}^2 \quad \text{or} \quad f_{yk} / f_{uk} > 0.8 \end{split}$$

### Displacements see Annex 18.

fischer injection system FIS V	
Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Reinforcing bars Characteristic values to shear load	Annex 27

<sup>2)</sup> In absence of other national regulations.

<sup>&</sup>lt;sup>3)</sup> The partial safety factor  $\gamma_2 = 1.0$  is included.



**Table 29:** Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009

Characteristic values to tension load for fischer rebar anchors FRA

Size		M12	M16	M20	M24		
Steel failure							
Characteristic resistance	N <sub>Rk,s</sub> [kN]	63	111	173	270		
Partial safety factor	γ <sub>Ms,N</sub> [-]	1,4					
Combined pullout and concrete failure							
Diameter of calculation	d [mm]	12	16	20	25		
Characteristic bond resistance in	concrete C20/25						
Temperature range I <sup>3)</sup> (-40°C / +80°C)	τ <sub>Rk,ucr</sub> [N/mm²]	11,0	10,0	9,5	9,0		
Temperature range II <sup>3)</sup> (-40°C /+120°C)	τ <sub>Rk,ucr</sub> [N/mm²]	9,0	8,5	8,0	7,5		
Factor for uncracked conxcrete	k <sub>ucr</sub> [-]	10,1					
	C25/30 [-]	1,05					
	C30/37 [-]	1,10					
Increasing factors	C35/45 [-]	1,15					
for $\tau_{_{\text{Rk},ucr}}$	C40/50 [-]	1,19					
	C45/55 [-]	1,22					
	C50/60 [-]	1,26					
Splitting failure							
	h / h <sub>ef</sub> ≥ 2,0	1,0 h <sub>ef</sub>					
Edge distance c <sub>cr,sp</sub> [mm]	2,0 > h / h <sub>ef</sub> > 1,3	4,6 h <sub>ef</sub> - 1,8 h					
	h / h <sub>ef</sub> ≤ 1,3						
Spacing	s <sub>cr,sp</sub> [mm]	2 c <sub>cr,sp</sub>					
Partial safety factor γ	$\gamma_{\text{Mp}} = \gamma_{\text{Mc}} = \gamma_{\text{Msp}}^{1}$ [-]		1,!	5 <sup>2)</sup>			

<sup>1)</sup> In absence of other national regulations.

Displacements see Annex 21.

fischer injection system FIS V	
Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009	Annex 28
fischer rebar anchor FRA	
Characteristic values to tension load	

<sup>&</sup>lt;sup>2)</sup> The partial safety factor  $\gamma_2 = 1.0$  is included

<sup>3)</sup> See Annex 2

English translation prepared by DIBt



**Table 30:** Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 Characteristic values to shear load for fischer rebar anchors FRA

Size		M12	M16	M20	M24	
Steel failure without lever arm	'					
Characteristic resistance	V <sub>Rk,s</sub> [kN]	30	55	86	124	
Partial safety factor	γ <sub>Ms,V</sub> [-]	1,56				
Steel failure with lever arm	•					
Characteristic bending moment	M <sub>Rk,s</sub> [Nm]	92	233	454	785	
Partial safety factor	γ <sub>Ms,V</sub> [-]	1,56				
Ductility factor	k <sub>2</sub> [-]	0,8				
Concrete pryout failure						
Factor in Equation (27) CEN/TS 1992-4-4, Section 6.3.3	k <sub>3</sub> [-]	2,0				
Partial safety factor	γ <sub>Mep</sub> [-]	1,5 <sup>2)</sup>				
Concrete edge failure		See CEN/TS 1992-4, Section 6.3.4				
Partial safety factor	γ <sub>Mc</sub> <sup>1)</sup> [-]	1,52)				

<sup>1)</sup> In absence of other national regulations.

Displacements see Annex 21.

Ì	fischer injection system FIS V	
	Design of Bonded Anchors acc. to CEN/TS 1992-4: 2009 fischer rebar anchor FRA Characteristic values to shear load	Annex 29

 $<sup>^{2)}</sup>$  The partial safety factor  $~\gamma_2^{}=$  1,0 is included.