

Approval body for construction products
and types of construction

Bautechnisches Prüfamt

An institution established by the Federal and
Laender Governments



European Technical Assessment

ETA-17/0773
of 21 December 2020

English translation prepared by DIBt - Original version in German language

General Part

Technical Assessment Body issuing the
European Technical Assessment:

Trade name of the construction product

Product family
to which the construction product belongs

Manufacturer

Manufacturing plant

This European Technical Assessment
contains

This European Technical Assessment is
issued in accordance with Regulation (EU)
No 305/2011, on the basis of

Deutsches Institut für Bautechnik

Schöck Isolink for multi-layer concrete panels

Glass fibre reinforced plastics (GFRP) connectors for use
in sandwich and element walls made of concrete

Schöck Bauteile GmbH
Vimbucher Straße 2
76534 Baden-Baden (Steinbach)
DEUTSCHLAND

Schöck Werk
Ringstraße 2
06188 Landsberg

17 pages including 3 annexes which form an integral part
of this assessment

EAD 330387-00-0601, Edition 03/2020

European Technical Assessment

ETA-17/0773

English translation prepared by DIBt

Page 2 of 17 | 21 December 2020

The European Technical Assessment is issued by the Technical Assessment Body in its official language. Translations of this European Technical Assessment in other languages shall fully correspond to the original issued document and shall be identified as such.

Communication of this European Technical Assessment, including transmission by electronic means, shall be in full. However, partial reproduction may only be made with the written consent of the issuing Technical Assessment Body. Any partial reproduction shall be identified as such.

This European Technical Assessment may be withdrawn by the issuing Technical Assessment Body, in particular pursuant to information by the Commission in accordance with Article 25(3) of Regulation (EU) No 305/2011.

Specific Part

1 Technical description of the product

The Schöck Isolink TA-H with nominal diameter of 12 mm is an anchor which consists of a glass fibre reinforce plastic bar. The anchor has a profile in the shape of a trapezoidal thread with a profile depth of 0.6 to 0.75 mm and a pitch of 8 mm. The ends of the TA-H anchor are inclined. The anchor is embedded on both sides in the concrete. It is orientated perpendicular to the wall. The product description is given in Annex A.

2 Specification of the intended use in accordance with the applicable European Assessment Document

The performances given in Section 3 are only valid if the GFRP connector is used in compliance with the specifications and conditions given in Annex B.

The verifications and assessment methods on which this European Technical Assessment is based lead to the assumption of a working life of the anchor channel of at least 50 years. The indications given on the working life cannot be interpreted as a guarantee given by the producer, but are to be regarded only as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

3 Performance of the product and references to the methods used for its assessment

3.1 Mechanical resistance and stability (BWR 1)

Essential characteristic	Performance
Resistance to GFRP failure under compression load	See Annex C1
Resistance to concrete failure under compression load	See Annex C1
Resistance to GFRP failure under tension load	See Annex C1
Resistance to concrete failure (cracked and uncracked concrete) under tension load	See Annex C1
Resistance to GFRP failure under shear load	No performance assessed
Resistance to concrete failure under shear load	No performance assessed
Maximum acceptable shear deformation	See Annex C1
Minimum edge distances and spacing	See Annex B2
Durability	See Annex B1
Modulus of Elasticity	See Annex B2
Geometric parameters	See Annex B2

4 Assessment and verification of constancy of performance (AVCP) system applied, with reference to its legal base

In accordance with EAD No. 330387-00-0601, the applicable European legal act is: [2000/273/EC].

The system to be applied is: 2+

5 Technical details necessary for the implementation of the AVCP system, as provided for in the applicable EAD

Technical details necessary for the implementation of the AVCP system are laid down in the control plan deposited with Deutsches Institut für Bautechnik.

Issued in Berlin on 21 December 2020 by Deutsches Institut für Bautechnik

Dipl.-Ing. Beatrix Wittstock
Head of Section

beglaubigt:
Müller




Fig. 1: Schöck Isolink® type TA-H
Wall with supported cover layer, thickness of insulation layer $60 \leq h_D \leq 350$ mm

Electronic copy of the ETA by DIBt: ETA-17/0773

Schöck Isolink® for multi-layer concrete panels

Product description
Installed condition with Schöck Isolink® type TA-H

Annex A1




Fig. 2: Schöck Isolink® type TA-HC
Wall with supported cover layer, thickness of insulation layer $60 \leq h_D \leq 350 \text{ mm}$

Schöck Isolink® for multi-layer concrete panels	
Product description Installed condition with Schöck Isolink® type TA-HC	Annex A2




Fig. 3: Schöck Isolink® type TA-H




Fig. 4: Schöck Isolink® type TA-HC

Schöck Isolink® for multi-layer concrete panels

Product description
Material and dimensions

Annex A3

B.1 Specifications of intended use

- Static and quasi-static loads in tension or compression in the direction of the longitudinal axis of the connector.

B.1.1 Base materials

- Reinforced normal-weight concrete according to EN 206-1:2000
- Strength classes C20/25 to C50/60 according to EN 206-1:2000
- Cracked or uncracked concrete

B.1.2 Use conditions (environmental conditions)

- Temperature on the surface of the concrete cover layer between -20°C and +65°C (maximum short-term temperature). Maximum long-term temperature is 40°C.

B.1.3 Design

- Connectors are designed under the responsibility of an engineer experienced in anchorages and concrete work.
- Verifiable calculation notes and drawings are prepared taking account of the loads to be anchored. The positions of the connectors are indicated on the design drawings (e.g. position of the connector relative to the reinforcement or to supports).
- The connectors are intended to be used for design analogous to EN 1992-4:2018.
- The actual shear deformation is limited to the maximum acceptable shear deformation according Annex C1

B.1.4 Installation requirements

- The installation of the connectors is carried out by appropriately qualified personnel under the supervision of the person responsible for the technical matters on site.
- Use of the connector as supplied by the manufacturer only – without manipulations or repositioning.
- Installation in accordance with the manufacturer's specifications given in Annex B4 to B9.

Schöck Isolink® for multi-layer concrete panels

Intended Use
Specifications

Annex B1

Table B.1: Installation parameters and layer thickness

Description	Abbreviation / Unit	Value	
Overall embedment depth of the connector in concrete	h_{nom} [mm]	≥ 60	
Minimum thickness of cover layer	$h_{v,min}$ [mm]	60	
Minimum thickness of insulation	$h_{D,min}$ [mm]	60	
Maximum thickness of insulation	$h_{D,max}$ [mm]	350	
Minimum thickness of structural layer	Element wall	60 (PC)	140 (In-situ concrete and PC)
	Sandwich wall	100	

Table B.2: Calculation values for connector Schöck Isolink®

Description	Abbreviation / Unit	Value
Nominal diameter	d [mm]	12
Nominal area (cross section)	A [mm ²]	113
Area moment of inertia around y axis	I_y [mm ⁴]	1161
Area moment of inertia around z axis	I_z [mm ⁴]	1161
Modulus of elasticity under normal force	E_N [N/mm ²]	60000
Modulus of elasticity under normal force	E_M [N/mm ²]	60000


Table B.3: Minimum edge distances and spacing

Description	Abbreviation / Unit	Overall embedment depth of the anchor in concrete h_{nom}	
		60 mm	100 mm
Minimum spacing ($=3,0 h_{nom}$)	s_{min} [mm]	180	300
Minimum edge spacing ($=1,5 h_{nom}$)	c_{min} [mm]	90	150

Schöck Isolink® for multi-layer concrete panels


Intended Use
Installation parameters

Annex B2




- Arrangement of Schöck Isolink® in a grid accordance with structural calculations, e.g spacing for 4 Schöck Isolink® per m²: $s_1 = s_2 = 50 \text{ cm}$.

Section A-A
Element wall:



Section A-A
Sandwich wall:



Section B-B
Element wall:





Fig. 5: Example of wall with supported cover layer
(Installation parameters in accordance with Annex B2)

Schöck Isolink® for multi-layer concrete panels

Intended Use
Example of wall with connectors

Annex B3




Fig. 6: Installation instruction - Schöck Isolink® for sandwich wall – page 1

Schöck Isolink® for multi-layer concrete panels

Intended use

Installation instruction for sandwich walls 1

Annex B4




Fig. 7: Installation instruction - Schöck Isolink® for sandwich wall – page 2

Schöck Isolink® for multi-layer concrete panels

Intended use

Installation instruction for sandwich walls 2

Annex B5




Fig. 8: Installation instruction - Schöck Isolink® for sandwich wall – page 3

Schöck Isolink® for multi-layer concrete panels

Intended use

Installation instruction for sandwich walls 3

Annex B6




Fig. 9: Installation instruction - Schöck Isolink® for element wall – page 1

Schöck Isolink® for multi-layer concrete panels

Intended use

Installation instruction for element walls 1

Annex B7




Fig. 10: Installation instruction - Schöck Isolink® for element wall – page 2

Schöck Isolink® for multi-layer concrete panels

Intended use
Installation instruction element walls 2

Annex B8




Fig. 11: Installation instruction - Schöck Isolink® for element wall – page 3

Schöck Isolink® for multi-layer concrete panels

Intended Use

Installation instruction element walls 3

Annex B9

Table C.4: Characteristic resistance under tension and compression load and acceptable shear deformation

Essential characteristic	Abbreviation	Concrete strength class	Thickness of insulation h_D	Overall embedment depth of the connector in concrete h_{nom}	
				60 mm	100 mm
Resistance to GFRP failure under compression load	$N_{Rk,GFRP,D}$	C20/25 to C50/60	250 mm	31,5 kN	
			350 mm	17,2 kN	
Resistance to concrete failure under compression load	$N_{Rk,c,D}$	C20/25 to C50/60	60 mm to 350 mm	20,4 kN	
Resistance to GFRP failure under tension load	$N_{Rk,GFRP}$	C20/25 to C50/60	60 mm to 350 mm	14,9 kN	
Resistance to concrete failure under tension load (uncracked concrete)	$N_{Rk,c,ucr}$	C20/25	60 mm to 350 mm	10,8 kN	25,5 kN
		C50/60		19,0 kN	42,4 kN
Resistance to concrete failure under tension load (cracked concrete)	$N_{Rk,c,cr}$	C20/25 to C50/60	60 mm to 350 mm	6,1 kN	
Maximum acceptable shear deformation	w_{max}	C20/25 to C50/60	60 mm	2,0 mm	
			100 mm	5,0 mm	

Schöck Isolink® for multi-layer concrete panels

Performance

Characteristic resistances and acceptable shear deformation

Annex C1